

Table of Contents

Page

v..... List of Figures

1.. INTRODUCTION 1

- 3.. Course Overview
 - .. Training Objectives
- 4.. The Reasons That Owners Retrofit
 - .. Many Buildings Need Retrofitting
- 5.. Retrofit Prescriptive Standards
- 6.. Prescriptive Retrofit Standards Work
 - .. When to Hire Professional Help

7.. EARTHQUAKE BASICS 2

- 9.. Earthquake Basics
 - .. Earthquakes & Faults
- 11.. Proximity To Faults
 - .. Surface Geology Effects
- 12.. Inertia Forces
 - .. Effect of Height on Building Movement
- 13.. Period of Vibration
- 14.. Horizontal Force Distribution
 - .. Base Shear and Cripple Walls
 - .. Horizontal Force-Resisting System
- 15.. Seismic Load Path in the Building
 - .. Gravity Force-Resisting System

17.. SHEAR WALLS - 3

- 19.. Getting the Big Picture
 - What is a Shear Wall?
 - Where Should Shear Walls Be Located?
- 21.. What Types of Forces Do Shear Walls Resist?
- 23.. What Are The Functions of a Shear Wall?
 - How Shear Walls Provide Strength
- 24.. Combining Different Material Strengths
- 25.. Shear Walls are like Wood I-Beams
- 26.. How Shear Walls Provide Stiffness
 - Stiffness and Aspect Ratios
- 26.. Allowable Aspect Ratio Table
- 27.. Lessons Learned from the Northridge Earthquake

- 27 ...Reduced Code Values Table
- 28 ...Success of Plywood Sheathing for Shear Walls
- 29 ...Wood Structural Panel Shear Walls
 - ...How to Install the Lumber
 -Use the Proper Lumber Species
 -Effect of Lumber Species on Strength Table
- 30Determine Existing Lumber Species
 -Use the Proper Size Stud
- 31Install Proper Size Blocking
- 32Properly Locate the Holdown Stud
- 33Use the Proper Lumber Grade and Size of Holdown Studs
 -Effect of Lumber Grade on Holdown Capacity Table
 -Avoid Mechanical Penetrations
- 35Evaluate Existing Lumber
- 36Provide Adequate Ventilation
- 37 ...How To Install The Sheathing
 -Use The Specified Wood Structural Panel
 -Oriented Strand Board
- 38Plywood
- 39Use The Proper Thickness & Number of Plies
 -Use The Proper Panel Grade
- 40Locate Panel on the Center of Framing Member & Blocking
- 41Use the Proper Size Panel
 -Mark Location of Studs on Panels
 -Maintain Fire Resistive and Sound-Rated Construction
- 42Provide Ventilation at Cripple Wall Sheathing
- 43 ...How To Install The Fasteners
 -Use Common Nails
 -Use the Proper Length of Common Nail
- 44Why Common Nails Are Important
 -Common vs. Box Nails Table
- 45Use Full Headed Nails
- 46Install Nails Flush to Sheathing
 -Provide Proper Sheathing Edge Distance
 -Center the Nails in the Framing Member and Blocking
- 47Check for Splitting of Lumber During Nailing
 -Remove All Improperly Installed Nails
 -Provide Proper Edge Nailing
 -How To Nail A Shear Wall Table

49 .. <u>CONNECTIONS - 4</u>	69 .. Foundation Condition
51 ... Connections Resisting Uplift Forces Deterioration
52 Types of Holdowns Foundation Cracking
... .. Importance of Proper Installation	70 .. Foundation Embedment
53 Common Holdown Installation Errors	.. Foundation Retrofit
54 Installation Errors for Bolted Holdowns Capping
... .. Improper End Distance Replacement
... .. Oversized Bolt Hole Parallel Systems
... .. Undersized Washers	71 .. <u>RETROFITTING POST & PIER HOUSES - 6</u>
... .. Substitution of Lag Screws for Through Bolts	73 .. Why Earthquakes Damage Post & Pier Houses
... .. Countersinking Nut & Washer	75 .. New Prescriptive Retrofit Method
55 Insufficient Depth of Embedment For Anchor Rods	.. Partial Perimeter vs. Continuous Foundation
... .. Substitution of Holdown Anchor Type	76 .. How Partial Perimeter Equals Continuous Foundation
... .. Untightened Nuts	77 .. Moisture Effects on Wood Materials
56 ... Connections Resisting Shear Forces	78 .. Holdown Anchors are Needed
... .. Fastener Types in Shear Connections	79 .. Transferring Forces to the Partial Foundations
57 Shear Connections in the Load Path	82 .. Evaluating Existing Conditions
... .. Non-Standard Framing	.. When you Need an Architect & Engineer
58 Connections at Top Plates	83 .. Partial Perimeter Retrofits Require More Attention to Detail
59 Connections at Sole Plates	.. Building Inspection Requirements
60 Connections at Sill Plate	.. Seismic Retrofitting Flood Prone Structures
61 Locating Drilled-In Anchors	85 ... <u>NON-STRUCTURAL ELEMENTS - 7</u>
... .. Provide Proper Edge Distance in the Concrete and Wood	87 .. Chimneys
... .. Provide Proper End Distance in the Sill Plate	88 .. Building Appendages
... .. Provide Proper Depth of Embedment in the Concrete	89 .. Veneer
62 Use the Proper Length of Anchor	90 ... Gas Lines
... .. Use Plate Washers	91 ... Water Heaters
... Installing Mechanical Anchors	92 ... Tanks
63 ... Installing Adhesive Anchors	93 ... Other Types of Nonstructural Items
... .. Carefully Clean the Hole	.. FEMA s Nonstructural Manual
... .. Use All-Threaded Rod	95 ... <u>SAFETY & LEGAL 8</u>
... .. Completely Fill the Hole in the Sill Plate with Adhesive	97 ... Safety On The Job Site
... .. Install the All-thread Rod with the Plate Washer and Nut Attached Wear Protective Clothing
... .. Wait Until Fully Cured Before Tightening Read and Follow MSDS
... .. Follow Safety Requirements Rope Off Dangerous Areas
64 ... Installing Side Plates Do Not Disturb Asbestos
... Interior Post to Girder Connections	99 .. Seismic Retrofit Legal Perspectives
... Putting It All Together	.. Earthquake Legal Basics
65 <u>FOUNDATIONS 5</u> Duty to Understand Earthquake Forces
67 ... Foundation Types	100 Agencies Have No Liability for Inspections
68 ... Foundation Material Prescriptive Standards
	101 Preconstruction Conferences
 Statutes of Limitations

102 Unlimited Exposure for Personal Injury	113 Keeping Track of the Work
.. Shear WallsNotification of Existing Conditions
.. Use Prescribed Wood and Shear Wall	114Change Orders
DimensionsInspections
.. Nailing PatternsPhotographs
103 Coordination is ImportantGetting Help
.. OSB	115 A Word About Warranties
.. Plywood StrengthWhen Should A Contractor Quit A Project
.. Use Specified Nails	
.. Nailing Patterns	117 <u>GLOSSARY</u>
104 Economics of Framing Affect Quality	
.. The Liability in Nailing Problems	123 <u>APPENDIX</u>
.. Connections A City of Los Angeles Prescriptive Standard
.. Holdowns B Real Estate Disclosure Requirements
.. ... Beware of Nonstandard Framing C Full Scale Nail Charts
105 Proper Anchor Bolt Assembly D Pre-Drilled Hole Sizes
.. ... Protection from Fumes E Partial Perimeter Foundation Details
.. Foundations and Miscellaneous Elements F Water Heater Bracing Illustrations
.. ... Need Effective Communication G Home Improvement Contract Form
.. ... Prejob Walk Through H Legal Aspects of Construction Administration
106Identify Differing Site Conditions	... I What Did You Learn
.. ...Legal Standards and Manufacturers Specs	
.. ...Continuity of Foundation	
.. ...Shoring	***
.. ...Concrete Quality and Owner Consultation	
107 .. Non-Structural Elements	
.. ...Care in Specification of Bracing	
109 .. A Contractor's Legal Relationship with the	
Customer	
.. ...Understanding the Owner s Concerns	
.. Money Limitations	
110Disruption to the Occupants	
.. ...Schedule	
.. ...Background Information	
.. Limiting A Contractor s Liability	
.. ...Necessary Documentation for Each Project	
.. Liability Insurance	
.. Project File and Documentation	
111 Employee and Subcontractor Screens	
.. Applicable Local Codes	
.. Preconstruction Walk Through	
.. The Importance of a Clear Written Contract	
.. Scope of Work Is Important	
.. Termination Options	
.. Exculpatory Provisions	
.. Liability Revolution	
.. Additional Work	
.. Get A Lawyer's Help with Your Contract	
.. Key Contract Provisions	
113Good Set of Plans	
.....Building Permit	

